


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-20285-00-00 Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County, Sec. 13 Twp. 10S Rge. 24W (~~W~~) (W)
Location as "NE/CNW%SW%" or footage from lines NW NE NW
Lease Owner Don E. Pratt Oil Operations
Lease Name Thelma Gano "A" Well No. 1
Office Address Drawer 370, Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 11-30-1969
Application for plugging filed 11-30-1969
Application for plugging approved 11-30-1969
Plugging commenced 11-30-1969
Plugging completed 11-30-1969
Reason for abandonment of well or producing formation No productible formation

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	209'	8 5/8"	209'	0

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned pits forming heavy mud - filled hole up to 1200 feet - spotted 100 sacks of cement @ 1200 feet - filled hole up to 245 feet - pushed bridge plug to 245 feet - spotted 25 sacks of cement @ 245 feet - filled hole up to 40 feet pulled half sack of hulls to 40 feet - filled hole with 10 sacks - cement to base of well cellar. Job complete 2:30 AM, November 30, 1969.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1969
CONSERVATION DIVISION
Wichita, Kansas
12-10-1969

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address Box 261, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James A. P. [Signature]
Box 261, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1969

My commission expires November 5, 1973

Richard [Signature]
Notary Public.

WELL LOG

15-065-20285-00-00

COMPANY Don E. Pratt Oil Operations

SEC. 13 T.10S R.24W

FARM Thelma Gano "A" No. 1


LOC. NW NE NW

TOTAL DEPTH 4030'

COUNTY Graham, Kansas

COMM. 11-23-69 COMP. 11-30-69

CONTRACTOR Garvey Drilling Company



CASING

8 5/8" @ 209' w/160sx

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 209' Surface Soil, Sand, & Shale
- 863' Shale & Sand
- 1640' Shale, Shells, & Sand
- 2012' Shale & Shells
- 2107' Shale
- 2148' Anhydrite
- 2425' Shale
- 2660' Shale & Lime Streaks
- 2880' Shale & Lime
- 3195' Shale & Lime Streaks
- 3312' Shale & Lime
- 3755' Lime & Shale
- 3870' Shale & Lime
- 3924' Lime & Shale
- 4030' Lime & Shale
- 4030' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 11 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 12-11-1969

State of Kansas }
 County of Barton } ss

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Thelma Gano "A" No. 1 well.

Charlene Marker

Subscribed and sworn to before me this 3rd day of December 1969

My Commission Expires: November 5, 1973

Richard Day
 NOTARY PUBLIC