


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 19 Twp. 10S Rge. 25W (E) (W)  
Location as "NE/CNW&SW" or footage from lines NW NE NE  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Krug "C" Well No. 1  
Office Address 780 Fourth National Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 5 1959  
Application for plugging filed June 5 1959  
Application for plugging approved June 5 1959  
Plugging commenced June 5 1959  
Plugging completed June 5 1959  
Reason for abandonment of well or producing formation No commercial quantities  
of oil found.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4305 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	219'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Set No. 1 Plug at 550' with 20 sacks  
cement; Set No. 2 Plug at 215' with  
20 sacks cement; Set No. 3 Plug at  
40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1959  
09-23-1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P  
780 Fourth National Bldg., Wichita 2, Kansas  
(Address)



Subscribed and sworn to before me this 29th day of July 1959  
Mona L. Latier  
Mona L. Latier Notary Public.

PLUGGING  
File Sec. 19 T 10 R 25W  
Book Page 22 Line 25

DRILLER'S LOG

**RECEIVED**  
STATE CORPORATION COMMISSION

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

15-065-02093-00-00

SEP 23 1959

CONSERVATION DIVISION

Krug "C" No. 1 Wichita, Kansas  
NW NE NE Sec. 19-10S-25W  
Graham County, Kansas

Total Depth: 4305'

Commenced: 5-26-59 Completed: 6-5-59

Elevation: 2562' R.B.  
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 219' with 175 sacks cement.

Figures indicate bottom of formations:

Surface Sand	219'
Shale-Sand & Shells	1000'
Shells & Shale	1770'
Dakota sand	1950'
Red Bed & Shale	2190'
Anhydrite	2226'
Shale	2250'
Shells & Shale	2590'
Shale & Lime	3858'
Lime	4305'
Total Depth	4305'

TOPS

Anhydrite	2190'	( 372 )
Heebner	3786'	( -1224 )
Toronto	3812'	( -1250 )
Lansing	3825'	( -1263 )
Base Kansas City	4060'	( -1498 )
Cherty Marmaton	4202'	( -1640 )
Cherokee	4263'	( -1701 )
Rotary Total Depth	4305'	( -1743 )

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Raymond L. Bacon  
Raymond L. Bacon-Vice-President

Subscribed and sworn to before me this 29th day of June, 1959.

My Commission Expires:



Moná L. Latier  
Moná L. Latier-Notary Public

**PLUGGING**

File Sec. 19-10-R-25W  
Book Page 2 Line 25