


15-065-00789-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Graham County, Sec. 21 Twp. 10S Rge. 25 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines: C SE SE NE  
Lease Owner Alva Oil Corporation, Inc.  
Lease Name Bollig Well No. 1  
Office Address 510 Fourth National Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed July 20 19 59  
Application for plugging filed August 3 19 59  
Application for plugging approved August 3 19 59  
Plugging commenced August 3 19 59  
Plugging completed August 3 19 59  
Reason for abandonment of well or producing formation non-commercial



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4275 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION               | CONTENT | FROM | TO | SIZE         | PUT IN      | PULLED OUT  |
|-------------------------|---------|------|----|--------------|-------------|-------------|
| <u>Base Kansas City</u> |         |      |    | <u>8 5/8</u> | <u>203</u>  | <u>none</u> |
|                         |         |      |    | <u>4 1/2</u> | <u>4093</u> | <u>1531</u> |
|                         |         |      |    |              |             |             |
|                         |         |      |    |              |             |             |
|                         |         |      |    |              |             |             |
|                         |         |      |    |              |             |             |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand to 4020; 3 sacks cement; mud to 290; rock bridge with 25 sacks cement; mud to 40; rock bridge with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1959  
08-19-1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address P. O. Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Arvel C. Smith, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arvel C. Smith, Jr.  
510 Fourth National Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of August, 19 59  
My commission expires 7-16-63  
Alma E. Ross  
Alma E. Ross Notary Public.



PLUGGING  
FILE SEC. 21 T 10 R 25  
BOOK PAGE 62 LINE 5

15-065-00789-00-00

DRILLERS LOG

No. 1 Bollig

CASING RECORD: COMPANY: Alva Oil Corp. Inc. DESCRIPTION: SE SE NE  
 8 5/8" @ 203\* CONTRACTOR: Red Tiger Drilling Co. 21-10-25W  
 w/135 sx cement Graham County  
 Kansas  
 COMMENCED: July 4, 1959  
 4 1/2" @ 4090\* ELEVATION: 2526 DF  
 w/125 sx COMPLETED: July 14, 1959 2529 RB

TOTAL DEPTH: 4275\*

| <u>FORMATION</u>  | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|-------------------|-------------|-----------|----------------|
| Surface Sand Clay | 0           | 130       |                |
| Shale             | 130         | 203       |                |
| Shale & Shells    | 203         | 1075      |                |
| Shale             | 1075        | 1200      |                |
| Sand Shale        | 1200        | 1580      |                |
| Shale & Shells    | 1580        | 2140      |                |
| Shale             | 2140        | 2168      |                |
| Anhydrite         | 2168        | 2202      |                |
| Red Bed Shale     | 2202        | 2520      |                |
| Shale & Shells    | 2520        | 2720      |                |
| Lime & Shale      | 2720        | 2912      |                |
| Lime Shale        | 2912        | 2985      |                |
| Lime & Shale      | 2985        | 3255      |                |
| Lime Shale        | 3255        | 3345      |                |
| Lime & Shale      | 3345        | 3480      |                |
| Shale & Lime      | 3480        | 3640      |                |
| Lime & Shale      | 3640        | 3815      |                |
| Lime              | 3815        | 4275      |                |


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING CO.

*George A. Angle*  
 \_\_\_\_\_  
 George A. Angle

Subscribed and sworn to before me this 22nd day of July, 1959.

*Maryne Head*  
 \_\_\_\_\_  
 Notary Public



My Commission Expires:  
 11-17-62

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 19 1959  
 08-19-1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 21 T 10 R254  
 BOOK PAGE 62 LINE 5