

API NUMBER 5-6-71

LEASE NAME Bollig

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

E 1/2 NE SE Ft. from S Section Line

         Ft. from E Section Line

SEC. 21 TWP. 10 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 5-6-71

Plugging Commenced 1-12-90

Plugging Completed 1-12-90

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4090

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	190	8 5/8		--
	Casing	0	4087	5 1/2		--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each section. Rig up Mercury. Find free point at 4030. Back off tubing at 4000'. Pull 10 joints. Rig up BJ Titan and pump 100 sacks 65/35 10% del, 2% A2 cement and 4000'. Pull 55 joints tubing. Pump 75 sks cement at 2000'. Pull 50 joints tubing. Pump 25 sacks cement at 500'. Pull 15 joints fill casing to surface with 2 sks cement. Hook up to annulus and pump 150 sks. Shut in 300#. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601 BJ Titan cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601

         day of January, 19 90

Rosemary Smith  
 Notary Public



STATE CORPORATION COMMISSION

My Commission Expires: 5-1/1991

JAN 16 1990  
 01-16-1990  
 CONSERVATION DIVISION  
 Wichita, Kansas