

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

03-01-1972
RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1972
CONSERVATION DIVISION
Wichita, Kansas

15-065-20425-00-00

Form CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Location as "NE/CNW/SE/SW" or footage from lines _____
Graham County, Sec. 21 Twp. 10 Rge. 25 (E) (W) X
SE/SE/NE

Lease Owner L. G. Stephenson
Lease Name Bollig Well No. 1
Office Address 360 Sutton Place Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2-3-72 _____ 19____
Plugging completed 2-7-72 _____ 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4080 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203	None
				5 1/2	4097	2165.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured T.D. Pushed a plug to 3850', dumped 25 ft. sand and 5 sacks cement. Shot casing at 3461, 3350, 3000, 2700, 2400, 2248 and 2150 ft. Pulled a total of 67 jts. of 5 1/2" casing. Allied squeezed well with 5 sacks hulls, 8 sacks gel, 110 cubic feet of 50/50 Pozmix with 6% gel, 19 sacks gel, 30 cubic feet Pozmix, 3 sacks gel, and 10 cubic feet Pozmix.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold James W. Rockhold
Box 698 Great Bend, Kansas 67530

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of February, 1972



Cathy Miller
Cathy Miller
Notary Public.

My commission expires September 30, 1972

15-065 - 20425-00-00

69

DRILLERS LOG

COMPANY: American Drilling Co., Ltd.
 CONTRACTOR: Company Tools
 FARM: Bollog No. 1
 LOCATION: Approx. 70' South of SE SE NE
 Section 21-10S-25W, Graham County
 COMMENCED: March 30, 1971
 COMPLETED: April 9, 1971

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 to 203'
Shale-Shells-Sand	203 to 1180'
Shale-Shells	1180 to 1835'
Red Bed	1835 to 2172'
Shale-Shells	2172 to 2820'
Lime-Shale	2820 to 3130'
Lime	3130 to 3654'
Lime-Shale	3654 to 4080'
Rotary Total Depth	4080'

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1972
 CONSERVATION DIVISION
 Wichita, Kansas

01-18-1972

REMARKS:

Set 8-5/8" surface casing at 203', cemented with 150 sacks cement. Plug down at 5:00 P.M. March 30, 1971.

- DST #1: 3798-3814'
- DST #2: 3865-3880'
- DST #3: 3948-3975'
- DST #4: 4015-4035'

Set 4-1/2" production casing at 4079' with 125 sacks cement. Plug down at 12:00 Noon April 9, 1971.

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF SEDGWICK)

SS:

I, Larry G. Stephenson, of the American Drilling Co., Ltd., do hereby certify and state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Larry G. Stephenson
 Larry G. Stephenson

Put on at 3906 to 15