

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-30198-00-00 Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 21 Twp. 10S Rge. (E) 25 (W)

Location as "NE/CNWxSWx" or footage from lines NW SE NE

Lease Owner Rains & Williamson Oil Co.

Lease Name Bollig Well No. 1

Office Address 1425 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-14 1966

Application for plugging filed 4-14 1966

Application for plugging approved 4-14 1966


Plugging commenced 4-14 1966

Plugging completed 4-14 1966

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Moreland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3833 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	187.79'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug in holes to 550'. Cement through drill pipe with 20 sx. Mud back and pushed plug in hole to 180'. Cement through drill pipe with 20 sx. Mud back to 40'. Set solid bridge and capped with 10 sx.

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1966
04-19-1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.


Wilson Rains, Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains, Partner
1425 Wichita Plaza Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of April, 19 66

Mary J. Brown
Mary J. Brown Notary Public.

My commission expires 3-3-1970



15-065-30198-00-00

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.
#1 Bollig
NW SE NE Sec. 21-10S-25W
Graham County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 4-9-66
Completed: 4-14-66
Remarks: Set 187.79' of 8-5/8" surface pipe with 140 sacks of GL3 cement.

FORMATIONS

Surface Clay	40'
Sand & Shale	120'
Shale	187'
Shale & Shells	410'
Shale	1755'
D. Sand	1944'
Shale & Red Bed	2075'
Shale	2172'
Anhydrite	2290'
Shale	2825'
Lime & Shale	3833'
Total Depth (D & A)	3833'

RECEIVED
STATE CORPORATION COMMISSION

04-19-1966
APR 19 1966

CONSERVATION DIVISION
STATE OF KANSAS

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 18th day of April, 1966.

My Commission Expires:
3-3-1970

Mary J. Brown
Mary J. Brown Notary Public

