

15-065-21058-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 28 Twp. 10S Rge. 25W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SW NE SW


Lease Owner Moble C. Hoover  
Lease Name Kenneth Knoll Well No. 1  
Office Address 302 NBC Bldg., El Dorado, Arkansas 71730  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed Nov. 15 1978  
Application for plugging filed (verbally) Nov. 15 1978  
Application for plugging approved (verbally) Nov. 15 1978  
Plugging commenced Nov. 15 1978  
Plugging completed Nov. 15 1978

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4090'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

T.D. 4090'  
Set 1st plug at 1050' with 70 sacks  
2nd plug at 240' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 2 sacks.

Cemented with 50/50 posmix, 6% gel.  
Plug was down at 8:30 p.m., 11-15-78.  
State Plugger - Gilbert Balthazor.

RECEIVED  
STATE CORPORATION COMMISSION  
11-21-1978  
NOV 21 1978

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 78



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires August 21, 1982

OPERATOR: Moble C. Hoover  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Kenneth Knoll #1  
 LOCATION: SW NE SW, Section 28-10S-25W  
 Graham County, Kansas  
 SPUD DATE: November 9, 1978  
 COMPLETION DATE: November 15, 1978

0	252	Surface Sand & Clay
252	1460	Sand & Shale
1460	2170	Shale
2170	2210	Anhydrite
2210	3084	Shale
3084	3468	Shale & Lime
3468	3968	Lime & Shale
3968	4090	Lime
	4090	Rotary Total Depth

Spud hole at 3:00 p.m., November 9, 1978. Drilled 257' of 12 1/4" hole. Ran 6 joints of 8 5/8" - 28# casing. (Tally 248') Set at 255' K.B. Cemented with 190 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 8:30 p.m., November 9, 1978.

T.D. 4090'. Set 1st plug at 1050' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 2 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 8:30 p.m., November 15, 1978.

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 21 1978  
 11-21-1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

SAMPLE TOPS:

Anhydrite 2170'  
 B/Anhydrite 2210'


STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc does hereby state that the above and foregoing is a true and correct copy of the log of the Kenneth Knoll #1, SW NE SW, Section 28-10S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 20th day of November 1978.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.