

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1967
12.07-67
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jay Clark of Dean and Clark, Incorporated has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Dean and Clark, Incorporated,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name: Schreiner Well No. 1

Location: SW-SW-SE Sec. 27 Twp. 10 Rge. (E)(W) 24

County Graham Total Depth 4040 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clark was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated.
Dakota section from 1150' to 1350'.

Circulate hole with heavy mud. Pull DP to 1370' and displace 100 Sx. cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

J. P. Roberts
Conservation Division Agent