

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. M. R. Fitzgerald of Texaco, Incorporated, has this date requested permission to plug the following described well:

Mr. Fitzgerald guarantees payment of the plugging fee.

Operator's full Name: Texaco, Incorporated,

Complete Address: Box #60, Hays, Kansas.

Lease Name: W. G. Culp Well No. 1

Location: CN $\frac{1}{2}$ -NE-NE Sec. 21 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4022 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fitzgerald was instructed to plug the well as follows:

325'--8 5/8" Surface pipe, cement circulated with 325 Sx.
4021'--4 1/2" Production casing cemented with 125 Sx. with
135 Bbl. oil and 135 Sx. gel ahead of cement. Well plugged
back to 4008'. Top perforations ~~xxx~~ at 3801.
Sand well back to 3790' and set 5 Sx. cement with dump bailer.
Pull 4 1/2" to 660' and circulate heavy gel mud. Pull 4 1/2" to 600'
and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 320' and dis-
place 20 Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @ 30' and
10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Lion Christy of Texaco, Inc. has this
date requested permission to plug the following described well:

Mr. Christy guarantees payment of the plugging fee.

Operator's full Name: Texaco, Inc.

Complete Address: 614 Bittling, Bldg. Wichita, Kansas

Lease Name: W.G. Culp Well No. 1

Location: Ch/r NE/4 Sec. 21 Twp. 10S Rge 24 (W)

County GRAHAM Total Depth 3900 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Christy was instructed to plug the well as follows:

CALL Mr. W.L. Nichols for
plugging instructions.

Very truly yours,
S. S. Gaudin
Conservation Division Agent