
J. Lewis Brock





## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bidg. 212 N. Market
WICHITA, KANSAS 67202

## VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

Administrator 500 Insurance Building Wichita, Kansas 67202 Dear Sir: Earl Morgan of Aspen Drilling Company. has this date requested permission to plug the following described well: Morgan guarantees payment of the plugging fee. Operator's full Name: Martin Explorations, Complete Address: 527 Union Center Building, Wichita, Kansas, Lease Name: Billings Well No. Location: 155' NE of SW-SW-NW Sec.23 Twp. 10 Rge. (E) (W) 24 County: Graham Total Depth 4015' Oil Well Gas Well Input Well SWD Well \_\_D & A \_\_X \_Lost Hole Mr. Morgan was instructed to plug the well as follows: 209'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 875'. Circulate hole with heavy mud. Pull DP to 1100 and displace 100 Sx. cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent