

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Millard Hebo of Hebo Casing has this date requested permission to plug the following described well:

Operator's Full Name: Don E. Pratt

Complete Address: 1011 Fort, Hays, Kans. 67601

Lease Name: Mc Call Well No. # 1-28

Location: Q-SE Sec. 28 Twp. 10 Rge. 24 (E) (W)

County: Graham Total Depth: 4010 ^{FT}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hebo was instructed to plug the well as follows:

8 5/8" - 172 ^{FT} SP. CU. / 140 ST ENT. -> 5 1/2" Set @ 4009 ^{FT} / 200 ST ENT.

No Plug Back - Perfs. Open Hole 1 ^{FT}.

Sand Bottom to 3550 ^{FT} - 1/2 ST ENT. -> Shot (2) Rec. 1700 ^{FT}.

Order 140 ST 50/50 Formix 4% GEL. - 3% Ca-Cl. + 25 ST GEL.

5 ST Halls - 8 5/8" Plug -> Pump In 8 5/8" with Pump Truck.

Put In - 4 ST Halls -> 15 ST GEL. -> 1 ST Halls -> 70 ST ENT. -> 10 ST GEL.

Release Plug. + 70 ST ENT. Very truly yours, (By allied Ent)

Max Pressure 300 ^{LBS} PSI

RECEIVED
STATE CORPORATION COMMISSION
M. J. [Signature]
Conservation Division Agent
DEC 31 1981