

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: McCall Well No. 1

Location: SE-SE-NW Sec. 28 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4010' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Voth was instructed to plug the well as follows:

156'--8 5/8" Surface casing, cement circulated with 150 Sx.  
4006'--4 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 3700' (Temp. Survey). Top perforation @ 3900'.

Push plug to 3850', sand back to 3825' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Sx. cement, staged.

Very truly yours,

Conservation Division Agent