



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

JAN 10 1974

CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Inc., has this

date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: National Oil Company & Amarex, Inc.,

Complete Address: Suite 550, 200 West Douglas, Wichita, Kansas.

Lease Name: McCall Well No. 1

Location: CSW-NE Sec. 28 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4025' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 110 Cu. Ft. cement thru DP. Pull DP to 225' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Handwritten signature of M. L. Nichols

Conservation Division Agent