

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 31 1981
12-31-81
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Millard Helbo of Helbo Casing has this date requested permission to plug the following described well:

Operator's Full Name: Don E. Pratt

Complete Address: 1011 Fort, Hays, Kans. 67601

Lease Name: McCull Well No. #3

Location: C-SW-NE Sec. 28 Twp. 10^s Rge. 24^w (E) (W)

County: Graham Total Depth: 4025^{ft}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Helbo was instructed to plug the well as follows:

8 5/8" - 218^{ft} SP. CU. 1/150st CNT. → 4 1/2" SET @ 4012^{ft} 1/200st CNT.
Plug Back T.O. 3980^{ft} → Helbo Pushed plug to 3900^{ft}
and 50^{ft} Sand 1/4st CNT. → shot (2) Recovered 3012^{ft}.
Order 140st 50/120 Forming 4% Gel. → 3% CHL. → 25st Gel. →
5st Hulls. and 8 5/8" Plug. = Pump In 8 5/8" with Pump Truck.
Put In 4st Hulls. → 13st GEL. → 1st Hulls. → 70st CNT. → 12st GEL.
Release Plug + 70st CNT. May Pressure → 450^{2.85} P.S.I

Very truly yours, (By allied CNT)
Maria Schmidt
Conservation Division Agent