

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,271-00-00

LEASE NAME Armbrister "C"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 11-30-85

Plugging Commenced 7:00 AM

Plugging Completed 9:00 AM

LEASE OPERATOR Petroleum Inc.

ADDRESS 300 W. Douglas Wichita, KS

PHONE# (316) 793-8371 OPERATORS LICENSE NO. 5238

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6 Hays, KS

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3998

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface hole	Sand & Shale	0	218	8 5/8	210	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

~~Plug @ 1800 - 20 sx, plug @ 950 - 100 sx, plug @ 250 - 40 sx, plug @ 40 - 10 sx
plug @ rathole 10 sx~~

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DNB Drilling, Inc. License No. 5476

Address 535 N. Oliver Wichita, KS 67208

STATE OF KANSAS COUNTY OF BARTON, ss.

Monte Chadd

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) Box 1447, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 85


My Commission Expires: 11-09-88
Juan D. Munz Notary Public

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1985
12-23-1985
CONSERVATION DIVISION

15-065-22271-00-00

D N B Drilling, Inc.



ROTARY CONTRACTOR DRILLING DEALS

J. L. DONELSON, PRES.
(316) 687-5471

535 NORTH OLIVER

WICHITA, KANSAS 67208

DRILLERS' LOG

Petroleum, Inc.
800 R.H. Garvey Bldg.
Wichita, KS 67202

Armbrister "C" #1
SE SE SE Sec. 28-10-22
Graham County, KS

Commenced: 11-23-85
Completed: 11-30-85

Surface casing: Ran 5 jts. 8 5/8", 20# new casing. Tallied 210.39', set @ 218'. Cemented with 175 sx 60/40 pozmix, 2% gel, 3% cc. Cement did not circulate. Cement down 60'. Cement with 100 sx.

FORMATION

Sand & Shale
Anhydrite
Shale
Lime

DEPTH

0-1759
1759-1807
1807-3410
3410-3998 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB Drilling, Inc.

By *J. L. Donelson*


STATE OF KANSAS: ss:

Subscribed and sworn to before me this 5th day of December, 1985.

Vicky L. Coppage, Notary Public

My appointment expires:
May 28, 1989

Vicky L. Coppage



RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1985
12-23-1985
CONSERVATION DIVISION