

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-22,8590000

LEASE NAME Armbrister

WELL NUMBER 1

330 Ft. from S Section Line

1,700 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 22 ~~W~~ or (W)

COUNTY Graham

Date Well Completed 11-21-02

Plugging Commenced 11-21-02

Plugging Completed 11-21-02

RECEIVED  
12-02-2002  
DEC 02 2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO BOX 1469, PLAINFIELD, IL 60544

PHONE (815) 609-7000 OPERATORS LICENSE NO. 3,293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-21-02 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3,765'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	209'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 1,760', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,100', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 260', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RUSSELL OIL, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

Contractor  
(Employee of ~~operator~~) or ~~operator~~


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 25th day of November, ~~2002~~ 2002

My Commission Expires: \_\_\_\_\_



Ruth Phillips  
Notary Public

Form 07




# Shields

Russell, Kansas

## WELL LOG

Operator: RUSSELL OIL, INC.  
 Well: ARMBRISTER #1  
 Commenced: November 15, 2002  
 Completed: November 22, 2002  
 Contractor: Shields Drilling Co.

Well Description: 50' West of SE SW SE  
 Sec. 28-10S-22W  
 Graham County, KS



CASING RECORD		
Size	Run	Pulled
8 5/8"	209'	Cmtd. w/150 sax

Elevation: 2,249' KB  
 Treatment:  
 Production: D & A

Tops:

RECEIVED  
 10-02-2002  
 DEC 02 2002  
 KCC WICHITA

..... Figures Indicate Bottom of Formations .....

Rock, shale & sand	212	
Sand & shale	1,585'	
Shale	1,740'	
Anhydrite	1,784'	
Shale	3,330'	
Shale & lime	3,665'	
Lime	3,765'	RTD

Notes