

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-22,212-00-00

LEASE NAME Webster

WELL NUMBER #1

990 Ft. from S Section Line

4390 Ft. from E Section Line

SEC. 26 TWP. 10 RGE. 22 (X) or (W)

COUNTY Graham

Date Well Completed 7-19-85

Plugging Commenced 7-19-85

Plugging Completed 7-19-85

LEASE OPERATOR National Development Co.

ADDRESS 205 E. Central, Suite 120 Wichita, KS 67202

PHONE#(316) 267-1331 OPERATORS LICENSE NO. 5114

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hay, Ks.
 to be filed

Is ACO-1 filed? by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3965

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1770' w/25 sacks 60/40 pozmix 6% gel thru drill pipe

Next Plug: @ 850' w/100 " " " " & 1 sack Cello Flake thru drill pipe

Next Plug: @ 250' w/40 sacks " " " thru drill pipe

Top Plug: @ 40' w/solid bridge of 1 sack Hulls & 10 sacks cement 15 sack in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

(Signature) Bill Draney


(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND CONSERVATION DIVISION before me this July day of July, 1985

Wichita, Kansas

Dorothy M. Hogue
 Notary Public

My Commission Expires: 4-29-86



15-065-2222-00-00

DRILLER'S WELL LOG

DATE COMMENCED: July 12, 1985
DATE COMPLETED: July 19, 1985

National Development Co.
WEBSTER #1
100' W of NE SW SW
Sec. 26, T10S, R22W
Graham County, Ks.

ELEVATION: 2263' K.B.

0 - 1759' Surface Soil, Shale, Post Rock
1759 - 1811' Anhydrite
1811 - 3277' Lime & Shale
3277 - 3485' Lime
3485 - 3489' Shale
3489 - 3509' Lime & Shale
3509 - 3750' Lime
3750 - 3883' Lime, Chert, Shale
3883 - 3965' Dolomite
3965' RTD

FORMATION DATA

Anhydrite 1759'
Topeka 3277'
Heebner 3485'
Toronto 3509'
Lansing 3524'
Base K.C. 3750'
Marmaton 3836'
Arbuckle 3883'
RTD 3965'

Surface Pipe: Set new
8-5/8", 20# pipe @252'
w/150 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.


Bill Draney

Subscribed and sworn to before me this 22 day of July 1985.

My Comm. Expires:

4-29-86

Lorathy M. Hagene
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1985
07-23-1985
CONSERVATION DIVISION
Wichita, Kansas