

15-065-21208-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 29 Twp. 10 Rge. 22 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines

SW SE NW  
Lease Owner F & M Oil Co., Inc.  
Lease Name Callison #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5/8/80 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 5/12/80 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted.

If a producing well is abandoned, date of last production  
19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4040'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	257	none
				4 1/2"	3785	3189'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded to 3550' and ran 4 sacks cement. Shot pipe at 3201', pulled 79 joints.  
Pumped 65 sacks cement, 3 sacks hulls, 10 sacks gel and 65 sacks cement, 50-50 pos,  
6%.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
05-23-1980  
MAY 23 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of May, 19 80

My commission expires



Margaret Melcher  
Notary Public.

15-065-21208-00-00

CONTRACTOR'S WELL LOG

OPERATOR: F & M Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Callison #1  
 LOCATION: SW SE NW, Section 29-10S-22W  
 Graham County, Kansas  
 SPUD DATE: March 05, 1980  
 COMPLETION DATE: March 13, 1980

0	260	Shale and sand
260	1357	Shale
1357	1861	Shale and sand
1861	1890	Anhydrite
1890	3035	Shale
3035	3280	Shale and lime
3280	3625	Lime and shale
3625	3680	Lime
3680	3793	Lime and shale
3793	3820	Shale and lime
3820	3939	Lime
3939	4035	Shale and lime
4035	4040	Lime and chert
	4040	Rotary Total Depth

Spud hole at 3:45 p.m., March 05, 1980. Drilled 260' of 12 1/4" hole. Ran 8 joints of 8-5/8" new 20# pipe. (Tally 250'). Set at 257' RTD. Cemented with 200 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 7:30 p.m., March 05, 1980.

T.D. 4040'. Ran 94 joints of 4 1/2" - 9 1/2# casing. (Tally 3790'). Set at 3785' with 125 sacks of common cement, 10 sacks salt and 5 sacks of salt flush ahead. Plug was down at 2:25 a.m., March 13, 1980.

*PBTD 3737 Perforations @ 3623-27 & 3664-68*

SAMPLE TOPS:

Anhydrite 1861'  
 B/Anhydrite 1890'

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY - 05 - 1980  
 CONSTRUCTION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Callison #1, SW SE NW, Section 29-10S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 18th day of March, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.