

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,182-00-00

LEASE NAME Stites

WELL NUMBER 1

SPOT LOCATION NW NE SW

SEC. 29 TWP. 10S RGE. 22W or (W)

COUNTY Graham

Date Well Completed 12-20-79

Plugging Commenced 3/14/85

Plugging Completed 3/19/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F & M OIL CO., INC.

ADDRESS 422 Union Center, Wichita, Kansas 67202

PHONE # (316) 262-2636 OPERATORS LICENSE NO. 5313

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 Hays Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing Depth to top 3628' bottom 3848' T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	273'	None
				4 1/2"	4098'	1519'
<u>Lansing</u>	<u>Oil & water</u>	<u>3628'</u>	<u>3848</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with 4 sacks cement, sand to 3675' & 4 sacks cement. Shot pipe at 2495', 2008', & 1519'. Pulled 38 joints of pipe. Plugged well with 4 hulls, 33 gel, 100 sacks cement, 7 gel, 8 5/8 plug, & 70 sacks 50/50 poz 6% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or _____

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 85



My Commission expires: _____

Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
03-22-1985
MAR 22 1985
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

15-065-21182-00-00

OPERATOR:
 CONTRACTOR:
 WELL NAME:
 LOCATION:
 SPUD DATE:
 COMPLETION DATE:

F & M Oil Company
 Abercrombie Drilling, Inc.
 Stites #1
 SW/4, Section 29-10-22
 Graham County, Kansas
 November 26, 1979
 December 07, 1979

0	274	Shale and sand
274	735	Shale
735	1430	Shale and sand
1430	1856	Shale
1856	1902	Anhydrite
1902	2622	Shale
2622	3535	Lime and shale
3535	3633	Shale and lime
3633	3672	Lime and shale
3672	4100	Lime
	4100	Rotary Total Depth

Spud hole at 5:45 p.m., November 26, 1979. Drilled 274' of 12 1/4" hole. Ran 9 joints of 8-5/8" used 24# casing. (Talley 266.31') Set at 273.61' with 180 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:00 midnight.

T.D. 4100'. Ran 102 joints of new 4 1/2" - 9.5# casing. (Talley 4103') Set at 4098'. Cemented with 150 sacks of common cement, 10% salt. Plug was down at 11:30 p.m., December 07, 1979.

SAMPLE TOPS:

Anhydrite 1856'
 B/Anhydrite 1902'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Stites #1, SW/4, Section 29-10-22, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 12th day of December, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.