

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas


15-065-02953-00-00
WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 34 Twp. 10 Rge. 22 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Wood River Oil & Refg. Co. Inc.

Lease Name Webster B Well No. 2

Office Address 335 W. Lewis St., Wichita Kans.

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date, well completed August 31 19 45

Application for plugging filed June 25 19 47

Application for plugging approved June 25 19 47

Plugging Commenced July 18 19 47

Plugging Completed July 22 19 47

Reason for abandonment of well or producing formation

Non-Commercial

If a producing well is abandoned, date of last production April 10 19 47

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough

Producing formation Kas. City Lime Depth to top 3575 Bottom 3610 Total Depth of Well 3971 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put-In	Pulled Out
Shale, Sd. & Anhyd.	Water	0	1805	8 5/8"	1805	None
Shale & Lime	Oil & Water	0	3969	5 1/2"	3969	2924'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole with bailer to 3610' ; Filled hole with mud to 3580' ;
Set a 75 ft cement plug from 3580' to 3505' with ten sacks cement.
Knocked 5 1/2" casing off at 2924' & pulled same.
Filled hole with mud to 1800' ; then set cement plug from 1800' to 1760' ,
with ten sacks cement.
Filled hole with mud from 1760 to 200' ; then set cement plug from 200' to
160' with ten sacks cement , then mudded hole to base of cellar and capped
same with ten sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Wood River Oil & Refg. Co.
Address 335 W. Lewis St., Wichita, Kans.

STATE OF Kansas COUNTY OF Sedgewick ss.
V. E. Wiggins (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

V. E. Wiggins

SUBSCRIBED AND SWORN to before me this 4th day of August 08-09-1947

Ruth N. Glass
Notary Public

My commission expires May 13, 1951



PLUGGING
FILE SEC 34 T 10 R 22 W
BOOK PAGE 122 LINE 23

Woodraver Oil Company
Webster # 2B

15-065-02953-00-00

Sec. 34 Twp. 10 Rge. 22
County: Graham, Kansas

Total Depth: 3971'
Comm: 7/25/45 Comp: 8/12/45

Casings:
70 jts. 8 5/8" set at 1802

Cement:
700 sacks.

Formations:	Depth:
Shale	115'
Sand & Shale	200
Shale & Shells	310
Sand	365
Shale	365
Sand	315
Sand & Shale	340
Hard Sand	385
Sand & Lime	1160
Sandy Lime & Shale	1165
Sand & Lime	1235
Sand, shales & red bed	1240
Sand & shells	1300
Redbed and shale	1700
Anhydrite	1835
Red bed and shale	2115
Red bed, shale & Lime	2315
Lime & shale	2500
Lime & shale brks.	2600
Shale & Lime	2765
Lime & shale brks.	2870
Lime & shale	3472
Lime & shale streaks	3580
Lime and shale	3700
Lime	3834
Lime	3810
Shale & Lime	3865
Lime & chert	3905
Shale & Lime	3965
Lime & chert	3971'

State of Kansas)
Russell County) 23

I hereby certify that the above information is true and correct to the best of my knowledge.

Clara Hummel

Subscribed and sworn to before me this 20th day of August 1945.

J. Genevieve Cook
Notary Public

My Commission expires July 2, 1949.

PLUGGING
FILE SEC 34 Twp. 10 Rge. 22
BOOK PAGE 22 LINE 23

FEE 1.00
02-19-1948