


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 3 Twp. 10S Rge. (E) 23 (W)

Location as "NE/CNW/SW" or footage from lines NE SW NW

Lease Owner Chief Drilling Co., Inc.

Lease Name KLENK Well No. 1

Office Address Box 797 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/7 1964

Application for plugging filed 9/7 1964

Application for plugging approved 9/7 1964

Plugging commenced 9/7 1964

Plugging completed 9/7 1964

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Moreland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3975 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	190'	8-5/8"	190'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set @ 600'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 180'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1964
09-14-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Box 797 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]* CHIEF DRILLING CO., INC.
Box 797 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of September, 1964

My commission expires Jan. 26, 1967

[Signature]
Carmen R. Cook
Notary Public.



15-065-01063-00-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

KLENK #1
NE SW NW Sec. 3-10S-23W
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 8/31/64
Completed: 9/7/64

Casing Record: 8-5/8" @ 190' w/145 sacks Sunset & 2 sacks Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Gravel	0	189	2433 Gr.
Shale & Cement	189	250	2435 D.F.
Shale & Sand	250	1290	2438 K.B.
Shale	1290	2007	
Anhydrite	2007	2055	
Shale & Shells	2055	2220	
Shale & Lime	2220	2550	
Lime	2550	2685	
Shale & Lime	2685	3310	
Lime	3310	3718	
Shale & Lime	3718	3751	
Lime	3751	3975	
Total Depth	3975		

<u>FORMATION TOPS</u>	
Anhydrite	2007 + 431
Heebner	3718 -1280
Toronto	3738 -1300
Lansing-Kansas City	3751 -1313
Base Kansas City	3973 -1535
Total Depth	3975 -1537

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE SW NW of Section 3-10S-23W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 10th day of September, 1964.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.



RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1964
09-14-1964
CONSERVATION DIVISION
Wichita, Kansas