


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 3 Twp. 10 Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines NE SE
Lease Owner Quality Supply Co.
Lease Name C. J. Klenke Well No. 1
Office Address 701 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2-28- 1962
Plugging completed 3-4 1962
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4310 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	195'	none
				7"	4310'	2494'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top Perforation 3925'

Sanded hole to 3690'-dumped 5 sks cement-
pulled casing to 550'-circulated mud to
top-spotted 30 sks cement-pulled pipe to 180'-
spotted 35 sks cement-finished pulling casing-
dumped 15 sks cement on top.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1962
03-19-1962
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jack Shear (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Shear
701 Union Natl. Bldg
(Address)

SUBSCRIBED AND SWORN to before me this 15 th day of March, 1962
Evelyn V. North
Notary Public.

My commission expires Dec 32, 1962




15-065-03310-00

Company- MAGNOLIA PETROLEUM
Farm- C. J. Klunk No. 1

SEC. 3 T. 10 R. 23
NE NE SE

Total Depth. 4257 P.B. 4188
Comm. 2-14-52 Comp. 3-7-52
Shot or Treated.
Contractor. Barnett Drlg.
Issued. 4-12-52

County Graham
KANSAS



Elevation. 2425 D.F.

Production. 8 bbis. / 1 wtr.

CASING:

13" 195'
6" 4236'

Figures Indicate Bottom of Formations.

surface	10
sand	40
shale	50
sand	185
shale & shells	1985
anhyd.	2030
shale & shells	2710
shale & lime	2825
shale & shells	2890
shale & lime	3105
shells, shale & lime	3155
lime & shale	3375
lime	3445
lime & shale	3490
lime	3555
lime & shale	3650
lime	4120
shale	4131
lime	4257
Total Depth	P.B. 4188

Tops:

Reebner	3682
Mansing	3718
Marmaton	3988
Congl.	4121
rb.	4234

D.S.T. 3741-56, open 1 hr., strong blow,
rec 330' sl. oil & heavily gas cut mud,
330' sl. gas & heavily oil cut mud, 30'
wtr. SI 15 min. BHP 700#.

P.B. 4188, perf. 4120-38 w/54 sh., bailed
9 GOPH, no wtr.
Stratafraced perfs. 4120-38 w/2000 gals.,
tested 17 hrs., 2 1/2 BUH no wtr.

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1962
03-19-1962
CONSERVATION DIVISION
Wichita, Kansas