

15-065-00760-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County. Sec. 3 Twp. 10 Rge. 23 (E) (W)

Location as "NE/CNW&SW" or footage from lines _____

Lease Owner Trans Era Petroleum, Inc.

Lease Name Klenk Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4/18/55 19

Application for plugging filed 4/17/55 19

Application for plugging approved 4/17/55 19


Plugging commenced 4/18/55 19

Plugging completed 4/18/55 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4174 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	226	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging Record

Filled hole with heavy mud to 210', 1 sack hulls & plug. 15 sacks cement through drill pipe on bottom plug. Filled hole to 40' with heavy mud, 1/2 hulls & plug to 40', 10 sacks of cement on top plug. Tied top plug to base.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.

Address Box 633, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.


H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis

(Address) _____, 19 55

SUBSCRIBED AND SWORN TO before me this 22nd day of April

My commission expires 1-30-57



Margie Cooper Notary Public.

PLUGGING
FILE SEC 3 T 10 R 23W
BOOK PAGE 113 LINE 39

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1955
04-28-1955
CONSERVATION DIVISION
Wichita, Kansas

15-065-00760-00-00

Trans Era Petroleum, Inc.
Klenk #1

SW SW SW 3-10-23
Graham County, Kansas

Total Depth: 4174

Comm: 4/3/55
Comp: 4/18/55

Casing

Cement

8 5/8" @ 226'

160 sacks of Atlas

FORMATION	DEPTH
Surface Clay & shale	70
Sand & shale	125
Shale & sand & shells	190
Shale & shells	265
Sand & shale	400
Shale & shells	550
Shale	710
Shale & shells	1260
Sand	1310
Shale	1370
Shale & Red Bed	1440
Sand	1515
Sand & shale	1750
Red Bed & shale	2005
Anhydrite	2040
Shale & shells	2310
Shale & lime	3494
Lime	3547
Shale & lime	3744
Lime	3975
Lime & shale	4174

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

Subscribed and sworn to before me this 26th day of April, 1955.

[Signature]

Notary Public



PLUGGING
FLX SEC 3 T 10 R 23W
BOOK PAGE 113 LINE 39

RECEIVED
CORPORATION COMMISSION
APR 28 1955
04-28-1955
CONSERVATION DIVISION
Topeka, Kansas