

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20395-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 12-11S-25W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: TIDBALL Well #: 7
County: TREGO Total Vertical Depth: 3960 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3959	0	w/175 sxs cmt
SURF	8.625	214	0	w/150 sxs cmt <u>128.70</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2008 12:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TERRY MORRIS Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shoot perfs at 2300' - 1970' - 1050' - 210'.
Operator chose to use all cement on this plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2008 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3700' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 2400' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 900' - circulated cement with 75 sxs cement out the 4 1/2" and the 8 5/8".
Pumped 5 sxs cement down the 4 1/2" to top off.

Perfs:

INVOICED
DATE 10/22/08
INV. NO. 2009060585

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 06 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #2167.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

CM

Form CP-2/3

OCT 02 2008

