

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20366-00-00

Spot: SE

Sec/Twnshp/Rge: 10-34S-40W

1327 feet from S Section Line, 1321 feet from E Section Line

Lease Name: MORGAN B

Well #: 2

County: MORTON

Total Vertical Depth: 3003 feet

Operator License No.: 5447

Op Name: OXY USA INC.

Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1171		WITH 2 SX CMT
PROD	4.5	3001	620	WITH 225 SX CMT
SURF	8.625	539		WITH 350 SX CMT

97.60

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/15/2008 8:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2725' & 2 SX CMT. STUB PLUG WITH 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/15/2008 4:00 PM

KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 1171' WITH 2 SX CMT. LOADED HOLE WITH 8 BBL MUD. PRESSURED TO 1700 PSI. RIH W/CIBP, COULDN'T GET BELOW 1175'. 1ST PLUG AT 590' WITH 50 SX CMT. 2ND PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2875	2877		
2858	2868		
2825	2847		

INVOICED

DATE 10/22/08

INV. NO. 2009060590

RECEIVED
KANSAS CORPORATION COMMISSION


Remarks: USED COMMON CEMENT BY SARGENTS.

OCT 01 2008

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed

Jack MacLaskey
(TECHNICIAN)