

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23445-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 25-10S-25W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: HOBBS Well #: 1
County: GRAHAM Total Vertical Depth: 4045 feet

Operator License No.: 33933
Op Name: POVERTY OIL LLC
Address: 2713 ASH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4044	3094	w/unknown sxs cmt
SURF	8.625	222	0	w/unknown sxs cmt

131.46

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2008 1:00 PM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: ED GLASSMAN Company: POVERTY OIL LLC Phone: (785) 259-5807

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 4% gel - 300# hulls.
TOC 3600'. Top production perf 3822'.
Sanded back to 3250'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2008 9:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded 5 1/2" casing back to 3250' w/5 sxs cement on top.
Log Tech shot casing off at 3094'.
Pulled 5 1/2" casing to 2200' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 1350' - pumped 100 sxs cement with 300# hulls.
Pulled casing to 275' - pumped 40 sxs cement cwc.
Pulled casing out of hole - topped off with 10 sxs cement.
Recovered 3094' 5 1/2" casing.

Perfs:

INVOICED
DATE 10/22/08
INV. NO. 2009060592

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 06 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

PRT

Form CP-2/3

OCT 02 2008