

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC Plugging
CP 2/3*

API Well Number: 15-015-19611-00-00
Spot: NWSENE Sec/Twnshp/Rge: 8-25S-5E
3932 feet from S Section Line, 965 feet from E Section Line
Lease Name: WILSON A Well #: 223
County: BUTLER Total Vertical Depth: 2451 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 2419 | | |
| SURF | 8.625 | 77 | | |

79-66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2008 8:00 AM
Plug Co. License No.: 31440 *33961* Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC LLC
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/23/2008 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
RIH W/TBG @ 2410, CONSOLIDATED MIXED & PUMPED 75 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 1,834'. RIH W/TBG @ 265', CONSOLIDATED MIXED & PUMPED 100 SXS CLASS A 3% CC. WAITED 2-HOURS, TAGGED CEMENT @ 596'. RIH W/TBG @ 265', CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A 3% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 2:30 PM. 9-24-2008. CONSOLIDATED CEMENT TICKET #18971.

Perfs:
INVOICED
DATE 10/22/08
INV. NO. 2009060599

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 06 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: T.O.C.-1600'. 5/15/1959. PUMP 300 SXS CEMENT DOWN 8-5/8"/5-1/2' ANNULUS. 11/61 FIXED CASING LEAKS @ 240' W/15 SXS, 550' W/60 SXS, 800' W/15 SXS.

Plugged through: TBG

District: 02 Signed *Duane Krueger*
(TECHNICIAN)

PKT