

KCCPKT6PS

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24451-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 13-20S-20E  
3352 ~~1955~~ Feet from N Section Line, 3951 feet from E Section Line  
Lease Name: MORGAN 8983 Well #: 10-T  
County: ANDERSON Total Vertical Depth: 750 feet

Operator License No.: 3113  
Op Name: MARTIN, CHRISTIAN DBA MARTIN OI  
Address: 6421 AVONDALE DR # 212  
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	22		6 SXCMT.

35.00

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2008 9:30 AM  
Plug Co. License No.: 8469 Plug Co. Name: NICKELL, RALPH DBA NICKELL DRILLING  
Proposal Rcvd. from: STACY MARTIN Company: MARTIN OIL PROPERTIES Phone: (405) 810-0900

Proposed Plugging Method: CEMENT PLUGS AT TD, FORT SCOTT (475 FEET), AND FROM 275 FEET TO SURFACE WITH GEL SPACERS.

Plugging Proposal Received By: LEVI SHORT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/05/2008 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

PLACE 1 INCH PIPE THROUGH BOREHOLE AND SET 50 FOOT CEMENT PLUG AT TOTAL DEPTH (750 FEET), 50 FOOT CEMENT PLUG AT 475 FEET, AND FILL FROM 275 FEET TO SURFACE WITH CEMENT. GEL SPACERS WERE PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 60 SACKS CEMENT.

RECEIVED  
KCC DISTRICT #3

MAY 6 2008 LS

CHANUTE, KS

INVOICED

DATE 10-23-08

INV. NO. 2009060603

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 19 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks:  
Plugged through: TBG

District: 03

Signed Levi Short 5/6/08  
(TECHNICIAN)

PS