

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-19201-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 30-13S-16W  
990 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: SANDER Well #: 7  
County: ELLIS Total Vertical Depth: 3577 feet

Operator License No.: 6127  
Op Name: KORON, JEFF DBA TAURUS OIL COMP  
Address: PO BOX 981  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3542	0	50 SX
SURF	8.625	215	0	150 SX

116.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2008 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JEFF KORON Company: TAURUS OIL COMPANY Phone: (785) 628-1727

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 4% gel - 600# hulls- 15 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/15/2008 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Pumped 50 sxs 60/40 pozmix - 4% gel down 5 1/2" with 300# hulls. - followed with 15 sxs gel spacer.  
Pumped 155 sxs 60/40 pozmix - 4% gel with 300# hulls.  
S.I.P. 300#. Visually verified cement on backside.

Perfs:

Top	Bot	Thru	Comments
3474	3478		

**INVOICED**  
DATE 10-23-08  
INV. NO. 2009060605

RECEIVED  
KANSAS CORPORATION COMMISSION  
**MAY 19 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34011.

Plugged through: CSG

District: 04

Signed

Pat Bedore

(TECHNICIAN)


CM

Form CP-2/3

MAY 15 2008

Pat

11-120 MAP NO. \_\_\_\_\_ SEC. 30-13S-16W  
 STATE Kans COUNTY Ellis LOC SE NW NE  
 OPER. Travis Brothers - Los Angeles, Calif. FT/FR \_\_\_\_\_ LINE  
 WELL 7 FARM Sander FT/FR \_\_\_\_\_ LINE  
 POOL Herzog ELEV. 1966 GR. 1968 OF 1971 KB  
 CONT. Leben Drlg. GEOL. George Reed  
 CO. INT. 3600' Test  
 F.R. 10-6-64 SPUD. 10-8-64 COMP. 11-10-64  
 TD. 3575 FM Arb PBTD. Est 3500  
 COMP. RECORD Arb 3474-78 16 natural  
 Co P 25 BOPD & est 25 BWPD  
 8 5/8" @215 w/150 sx. 5 1/2" @3542 w/50 sx. *Data Inc.*



(KB Log)	DST #1 (KC) 3234-80, Op 1/2 hr, R 25' M,
Anh 1098 / 873	No ISIP, IFP 59#, FFP 79#, FSIP 247#/20",
Hb 3179 -1208	DST #2 (Arb) 3482-92, Op 45", Str blo, R,
Tor 3200 -1229	1475' OC sulf wtr, ISIP 756#/20", IFP
KC 3228 -1317	114#, FFP 651#, FSIP 741#/20", GSO &
BKc not called	por in top 10' oc Arb 3472-82, RTD 3575,
Arb 3472 -1501	Ran Log, 5 1/2" @3542 w/50 sx., MICT, CO,
LTD 3575 -1604	Perf 16/3474-78 (Arb), § 5 1/2 BFPH (50%
	oil)/9 hrs, nat, POP, Co P 25 BOPD & est
	25 BWPD, Arb 3474-78 - COMPLETED (11-5-64)