

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-27621-00-00

Spot: NENENE

Sec/Twnshp/Rge: 32-30S-16E

380 feet from N Section Line,

620 feet from E Section Line

Lease Name: UNIT 1- CRAMER

Well #: CR 39P-N

County: WILSON

Total Vertical Depth: 800 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176

INDEPENDENCE, KS 67301

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
SURF	6.625	40		

35.00

Well Type: DH

UIC Docket No:

Date/Time to Plug: 09/18/2008 1:00 PM

Plug Co. License No.: 33961

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC

Proposal Rcvd. from: JURGEN J. HANKE

Company: AX & P, INC

Phone: (620) 325-5212

Proposed Plugging Method: Run cement string to TD and fill from btm to top with cement and gel spacers.

Plugging Proposal Received By: ALAN DUNNING

Witness Type: PARTIAL

Date/Time Plugging Completed: 09/18/2008 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

10 sacks of cement was placed at 750'. The cement string was raised to 500' and 10 sacks of cement was spotted. The cement string was raised to 250' and the well filled from 250' to surface with cement. Gel spacers were used between cement plugs. A total of 44 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DISTRICT #3

OCT - 7 2008

CHANUTE, KS

AMP

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 09 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10-24-08
INV. NO. 2609060608

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

PKT