

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-10004-00-00⁰²
Spot: SWSWSE Sec/Twnshp/Rge: 13-31S-9W
291 feet from S Section Line, 2293 feet from E Section Line
Lease Name: F W GRABS B Well #: 1
County: HARPER Total Vertical Depth: 4479 feet

Operator License No.: 5429
Op Name: HAYES, BRYCE F. DBA BRYCE F. HAY
Address: 1081 W HWY 160 PO BOX 108
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4479		
SURF	9.726	200		
T1	2.875	3787		

145,57

Well Type: SWD UIC Docket No: D07755.0 Date/Time to Plug: 09/24/2008 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BRYCE F HAYES Company: BRYCE F HAYS O&G Phone: (620) 254-7943

Proposed Plugging Method: PERF THRU TUBING AT 1500', PUMP 35 SKS CMT, PERF 900', PUMP 35 SKS CMT. PERF AT 250' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2008 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SQUEEZED OFF WHEN THE TUBING WAS CEMENTED IN THE HOLE, DUE TO THE FAILURE OF THE PAKER SHOE ON THE BOTTOM OF THE TUBING, THE PERFORATOR WAS RUN IN THE HLE TO 1500', WHERE 4 SHOTS WERE PLACED. THE PMP TRUCK WAS TIED ONTO TUBING AND CIRCULATION RATE WAS ESTABLISHED AT 3BBLs/MIN AT 1000#. PUMPED 35 SKS OF COMMON 2% CACL. DISPLACED TO 560' BEFORE WELL SQUEEZED OFF AT 1200#. 1-2 BBLs OF CMT OUTSIDE 5.5 CASING. PERFORATED CASING AT 540', ESTABLISHED CIRCULATION ON CASING AND BRADEN HEAD. CEMENT WAS CIRCULATED FROM 540'-0' UP THE TUBING-CASING ANNULAS. CEMENT WAS THEN CIRCULATED UP THE BRADEN HEAD FROM 540'-0'.

Perfs:

INVOICED
DATE 10-24-08
INV. NO. 2009060607

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING TICKET #32443 COMMON 3% CACL AND 60/40 POZ

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

[Signature]