

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22169-00-00  
Spot: NESE Sec/Twnshp/Rge: 33-27S-7W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: GONZALES Well #: 1-33  
County: KINGMAN Total Vertical Depth: 4419 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	239		

143.62

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2008 3:00 PM

Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.

Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING Phone: (620) 786-7133

Proposed Plugging Method: 35 SKS ARB, 35 SKS 1200, 35 SKS 700, 35 SKS 285, 25 SKS 60', 15 SKS RH

Plugging Proposal Received By: VIRGIL CLOTHIER  
Date/Time Plugging Completed: 09/27/2008 6:00 PM

Witness Type: NONE  
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE DRILL PIPE WAS RUN OPEN END TO 1200', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 285', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 60', WHERE CMT WAS CIRCD TO SURFACE. THE RAT HOLE WAS CIRC WITH 15 SKS OF CMT.

Perfs:

**INVOICED**  
DATE 10-24-08  
INV. NO. 2009060609


RECEIVED  
KANSAS CORPORATION COMMISSION  
**OCT 09 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CMTG 32502 60/40 POZ 4% GEL

Plugged through: DP

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

