

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23746-00-00
Spot: NW NESW Sec/Twnshp/Rge: 33-17S-21W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: CASEY Well #: 1-33
County: NESS Total Vertical Depth: 4217 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1472		WITH 375 SX CMT
PROD	4.5	4204	0	WITH 125 SX CMT
SURF	8.625	237		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2008 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: PUMP 200# HULLS WITH FIRST OF CMT, FILL CASING WITH CMT. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2008 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 275 SX CMT & 200# HULLS IN WITH FIRST OF CMT. MAXIMUM PRESSURE 2400#. SHUT IN PRESSURE 2000#. TIED ONTO BACKSIDE AND PRESSURED RIGHT UP TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4204	4217	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 09 2008
CONSERVATION DIVISION
WICHITA, KS


INVOICED

DATE 10-24-08
INV. NO. 2009060610

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

Form CP-2/3

PLS