

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20199-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1969
CONSERVATION DIVISION
Wichita, Kansas
01-28-1969

Operator's Full Name Don E. Pratt,

Complete Address: Drawer "D", Hays, Kansas.

Lease Name Elmer Gano Well No. 3

Location CNE Sec. 11 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4058'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.

Operation Completed: Hour 1:30 AM Day 25 Month 1 Year 1969

The Above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1/28/69

INV. NO. 9244-u