

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20265-00-00

10-20-1969  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Elmer Gano Well No. 4

Location SE-SE-NE Sec. 11 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4027'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Garvey Drilling Company,

Address Box #261, Great Bend, Kansas. License No.     

Operation Completed: Hour 1:00 PM Day 14 Month 10 Year 1969

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru  
DP from 1200' to 875'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/20/69  
INV. NO. 688-W

Signed: W. L. Nichols  
Well Plugging Supervisor