

KANSAS

*AL*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

*15-065-20226-00-00*

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
*05-26-1969*

Operator's Full Name Beacon Resources Corporation,

Complete Address 312 Union Center Building, Wichita, Kansas.

Lease Name Pfeifer Well No. 1

Location NE-NE-NW Sec. 11 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4080'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 12:00 PM Day 23 Month 5 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 100 Sx. cement thru  
DP from 1240' to 915'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Dichek*  
Well Plugging Supervisor

DATE 5/29/69  
INV. NO. 9838-4