

KANSAS

14

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20293-00-00

12-22-1969

Operator's Full Name George A. Reed

Complete Address 1223 Union National Bank Building, Wichita, Kansas.

Lease Name Gano Well No. 2

Location E/2-E/2-SE Sec. 11 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor C & G Drilling Company,

Address 1107 Union National Bank Building, Wichita, Ks. License No.

Operation Completed: Hour 12:30 PM Day 20 Month 12 Year 1969

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 825'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 12-22-69

INV. NO. 1095-W