

KANSAS

*J* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1971  
CONSERVATION DIVISION  
Wichita, Kansas

05-14-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20437-00-00

Operator's Full Name Don E. Pratt,  
Complete Address Drawer #370, Hays, Kansas.  
Lease Name Frank Pfeifer Well No. 1  
Location SE-SE-NW Sec. 11 Twp. 10 Rge. (E) (W) 24  
County Graham Total Depth 3864'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Dreiling Oil, Incorporated,  
Address R. R. #2, Victoria, Kansas. License No.         
Operation Completed: Hour 12:00 PM Day 10 Month 5 Year 1971

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru  
DP from 1200' to 875'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. S. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 5/14/71  
INV. NO. 3697-W