

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
03-07-1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

30061-00-01  
15-065-~~2025~~-00-00

Operator's Full Name Don E. Pratt.

Complete Address Drawer #370, Hays, Kansas.

Lease Name Elmer Gano Well No. 2

Location NE-NE-NE Sec. 11 Twp. 10 Rge. (E) (W) 2h

County Graham Total Depth 4053'

Abandoned Oil Well       Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 7:15 PM Day 2 Month 3 Year 1974

The above well was plugged as follows:

App:200'-8 5/8" Surface casing cement circulated.  
4049'-4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to  
4025'. Top perforations from 3850' to 3854'.

Pushed plug to 3800' and sanded well back from 3800' to 3750' then set 4 Sx. cement  
with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls  
and 12 sacks gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 15  
sacks gel from 825' to 225' and followed with 30 Cu. Ft. cement from 225' to 150'  
then 3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom  
of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-50#. (Mudding  
and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 3/12/74

INV. NO. 8737-W