

KANSAS

18
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20397-00-00

12-08-1970
RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don E. Pratt Oil Operations,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Barney McCoy Well No. 1

Location NW-NW-SE Sec. 13 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3545'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 3:00 AM Day 6 Month 12 Year 1970

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1120' and displaced 100 Sx. cement thru
DP from 1120' to 800'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from
185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/8/70
INV. NO. 3020-W

Signed: *K. L. Nichols*
Well Plugging Supervisor