

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas
12-02-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20285-00-00

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Thelma Gano Well No. A-1

Location NW-NE-NW Sec. 13 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4030'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Box #261, Great Bend, Kansas. License No.

Operation Completed: Hour 2:30 AM Day 30 Month 11 Year 1969

The above well was plugged as follows:

2091--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/2/69
INV. NO. 951-W