

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
06-12-1970

15-065-20334-00-00

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Thelma Gano Well No. B-1

Location SE-SE-NE Sec. 13 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4033'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.     

Operation Completed: Hour 7:00 PM Day 9 Month 6 Year 1970

The above well was plugged as follows:

187'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru  
DP from 1050' to 725'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 6/12/70  
INV. NO. 2037-4