

KANSAS

Y STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Free'd
11-14-1972

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20570-00-00

Operator's Full Name Hinkle Oil Company,
Complete Address 1016 Union Center, Wichita, Kansas.
Lease Name Walt Well No. 1
Location SW-SW-NW Sec. 19 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 3815'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza, Wichita, Kansas. License No.
Operation Completed: Hour 8:30 AM Day 11 Month 11 Year 1972

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed:

W. L. Deibel
Well Plugging Supervisor

INVOICED

DATE 11/14/72

INV. NO. 6632-W