

KANSAS

Form CP-3
Rev. 6-4-68

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20356-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas
08-10-1970

Operator's Full Name Beacon Resources Corporation,
Complete Address 1000 Century Plaza, Wichita, Kansas.
Lease Name Walt Well No. 1
Location NW-NW-NW Sec. 19 Twp. 10 Rge. (E) (W) 25
County Graham Total Depth 2250'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor B & B Drilling, Incorporated,
Address 207 Petroleum Building, Wichita, Kansas. License No.
Operation Completed: Hour 4:15 PM Day 7 Month 8 Year 1970

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 220' and displaced 25 Sx. cement thru DP from 220'
to 145'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 8/10/70
INV. NO. 2349-W