

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20717-00-00

OCT 15 1974
10-15-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Oil Company,

Complete Address Suite 550, 200 West Douglas, Wichita, Kansas.

Lease Name Buschauer Well No. 1

Location CNW-NW Sec. 11 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4040'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.

Operation Completed: Hour 7:15 PM Day 12 Month 10 Year 1974

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
Thru DP from 1125' to 800'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/16/74

INV. NO. 113-W