

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
01-24-1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20644-00-00

Operator's Full Name National Oil Company,  
Complete Address Suite 500, 200 West Douglas, Wichita, Kansas.  
Lease Name LaCerte Well No. 1  
Location NW-NW-SW Sec. 21 Twp. 10 Rge. (E) (W) 25  
County Graham Total Depth 3845'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor John O. Farmer, Incorporated,  
Address 370 W. Wichita, Russell, Kansas. License No.         
Operation Completed: Hour 12:30 PM Day 21 Month 1 Year 1974

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 110 Cu. Ft. cement  
thru DP from 1350' to 1025'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Daniels  
Well Plugging Supervisor

DATE 1/24/74  
INV. NO. 8448-W