

KANSAS

Form CP-3
Rev. 6-4-68

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

04-30-1971
RECEIVED
STATE CORPORATION COMMISSION
APR 30 1971
CONSERVATION DIVISION
Wichita, Kansas

15-065-20435-00-00

Operator's Full Name Dreiling Oil, Incorporated.

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Walch Well No. 1

Location NW-NW-NE Sec. 30 Twp. 10 Rge. (E) (W)25

County Graham Total Depth 4098'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:00 AM Day 26 Month 4 Year 1971

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/30/71
INV. NO. 3631-W

Signed: *W. L. Dickels*
Well Plugging Supervisor