

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1972
05-24-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20547-00-00

Operator's Full Name F & M Oil Company,
Complete Address 603 Union Center, Wichita, Kansas.
Lease Name Faulkner Well No. 1
Location CNE-NE Sec. 28 Twp. 10 Rge. (E) (W) 22
County Graham Total Depth 3810'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Hellar Drilling Company, Inc.,
Address 339 Union Center, Wichita, Kans. License No. _____
Operation Completed: Hour 12:00 M Day 22 Month 5 Year 1972

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 5/25/72
INV. NO. 5949-W