

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20532-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1972
CONSERVATION DIVISION
Wichita, Kansas
03-13-1972

Operator's Full Name Petroleum, Incorporated,
Complete Address 300 West Douglas, Wichita, Kansas.
Lease Name Fritts Well No. B-1
Location CNE-NE Sec. 29 Twp. 10 Rge. (E) (W) 22
County Graham Total Depth 3858'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Garvey Drilling Company,
Address Box #1164, Great Bend, Kansas. License No.
Operation Completed: Hour 7:45 AM Day 10 Month 3 Year 1972

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru DP
from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3/13/72
INV. NO. 5330-W