

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-065-20199-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JAN 28 1969

CONSERVATION DIVISION  
Wichita, Kansas

1-28-1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer "D", Hays, Kansas.

Lease Name: Elmer Gano Well No. 3

Location: CNE Sec. 11 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 4058. Oil Well ---

Gas Well --- Input Well --- SWD Well --- D & A X Lost Hole ---

Mr. Zorn was instructed to plug the well as follows:

185'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent